

Dandara - Ballasalla Phase 4 - Priced Groundwork Schedule

			Qty	Unit	Rate	R Ext £ p
EXTERNAL WORKS						
1	Excavation, reduce level dig maximum depth exceeding 1.00m		428	m³	3.16	1,352.48
A010005089	Excavator Operator		0.06	hour	24.77	1.49
G000010003	21 tonne excavator FOX (no fuel)		0.06	hour	17.78	1.07
G000035085	White diesel fuel		0.12	litre	1.55	0.19
2	Disposal - deposit on site in temporary spoil heaps		428	m³	5.27	2,255.56
A010005081	Skilled Groundworks Labourer		0.10	hour	22.50	2.25
G000035085	White diesel fuel		1.00	litre	1.55	1.55
G000020005	9 tonne dumper FOX (without operator & fuel)		0.10	hour	7.78	0.78
3	Disposal off site		428	m³	35.44	15,168.32
Y000010013	Cart and tip inert excavated material from South area at Fairgreen Tip (loading wagons by Main Contractor machine)		1.90	tonne	16.22	30.82
4	Filling - Type 1 material in 150mm layers, avg thickness exceeding 0.25m		433	m³	60.28	26,101.24
A010005089	Excavator Operator		0.13	hour	24.77	3.22
D000100101	Type 1 from Billown delivered to Peel area by Fairgreen		1.96	tonne	23.72	46.49
G000010003	21 tonne excavator FOX (no fuel)		0.13	hour	17.78	2.31
G000035085	White diesel fuel		0.26	litre	1.55	0.40
5	Filling - Type 6F2 material in 150mm layers, avg thickness exceeding 0.25m		908	m³	40.00	36,320.00
A010005089	Excavator Operator		0.13	hour	24.77	3.22
D000100104	6F2 from AV Craine delivered to Peel area by Fairgreen		1.96	tonne	14.72	28.85
G000035085	White diesel fuel		0.26	litre	1.55	0.40
G000010003	21 tonne excavator FOX (no fuel)		0.13	hour	17.78	2.31
6	Compacting - bottom of excavation		2029	m²	0.68	1,379.72
A010005081	Skilled Groundworks Labourer		0.02	hour	22.50	0.45
G000035032	Twin drum ride on roller FOX (without op & fuel)		0.02	hour	5.56	0.11
G000035085	White diesel fuel		0.02	litre	1.55	0.03
7	Compacting - type 6F2 material		2029	m²	1.05	2,130.45
A010005081	Skilled Groundworks Labourer		0.03	hour	22.50	0.68
G000035085	White diesel fuel		0.04	litre	1.55	0.06
G000035032	Twin drum ride on roller FOX (without op & fuel)		0.03	hour	5.56	0.17
8	Compacting - 50mm sand blinding		1681	m²	0.71	1,193.51
A010005081	Skilled Groundworks Labourer		0.02	hour	22.50	0.45
G000035032	Twin drum ride on roller FOX (without op & fuel)		0.02	hour	5.56	0.11

Dandara - Ballasalla Phase 4 - Priced Groundwork Schedule

			Qty	Unit	Rate	R Ext £ p
G000035085	White diesel fuel		0.04	litre	1.55	0.06
9	Terram T1000, one layer		2029	m²	0.00	0.00
10	Precast - Kerbs type bullnose 125x150mm, bed & haunch, straight runs		398	m	41.48	16,509.04
A010005082	Skilled Groundworker		0.15	hour	30.00	4.50
A010005081	Skilled Groundworks Labourer		0.15	hour	22.50	3.38
F001100090	C25 IAGG rate		0.07	m3	168.51	11.80
F003500015	125 x 150mm PCC kerb		1.05	m	9.57	10.05
G000101000	Premix mortar		2.10	litre	0.32	0.67
G000010020	5 tonne excavator with operator and fuel		0.12	hour	44.98	5.40
G000050030	Cut off saw		0.15	hour	1.83	0.27
11	Precast - Kerbs type bullnose 125x150mm, bed & haunch, radius runs		49	m	47.37	2,321.13
A010005082	Skilled Groundworker		0.17	hour	30.00	5.10
A010005081	Skilled Groundworks Labourer		0.17	hour	22.50	3.83
F003500016	125 x 150mm PCC kerb; 1500mm radius		1.05	m	14.16	14.87
F001100075	C15 IAGG Rate		0.07	m3	157.83	11.05
G000101000	Premix mortar		2.10	litre	0.32	0.67
G000010020	5 tonne excavator with operator and fuel		0.12	hour	44.98	5.40
G000050030	Cut off saw		0.15	hour	1.83	0.27
12	Precast - Kerbs type half battered HB2 125x225, bed & haunch, straight runs		40	m	41.38	1,655.20
A010005082	Skilled Groundworker		0.12	hour	30.00	3.60
A010005081	Skilled Groundworks Labourer		0.12	hour	22.50	2.70
F003500027	255 x 125mm HB2 kerb		1.05	m	11.96	12.56
G000101000	Premix mortar		2.10	litre	0.32	0.67
F001100075	C15 IAGG Rate		0.07	m3	157.83	11.05
G000010020	5 tonne excavator with operator and fuel		0.12	hour	44.98	5.40
13	Precast - Kerbs type half battered HB2 125x150, extra for angle		8	nr	41.72	333.76
A010005082	Skilled Groundworker		0.15	hour	30.00	4.50
A010005081	Skilled Groundworks Labourer		0.05	hour	22.50	1.13
F003500021	125 x 255mm PCC kerb, external corner		1.00	nr	24.00	24.00
F001100075	C15 IAGG Rate		0.04	m3	157.83	6.31
G000101000	Premix mortar		1.05	litre	0.32	0.34
14	Precast - Kerbs type half battered HB2 125x255, extra for quadrant		8	nr	43.02	344.16
A010005082	Skilled Groundworker		0.15	hour	30.00	4.50
A010005081	Skilled Groundworks Labourer		0.05	hour	22.50	1.13
F001100075	C15 IAGG Rate		0.04	m3	157.83	6.31

Dandara - Ballasalla Phase 4 - Priced Groundwork Schedule

			Qty	Unit	Rate	R Ext £ p
F003500065	305 x 255 mm PCC quadrant		1.00	nr	25.13	25.13
G000101000	Premix mortar		1.05	litre	0.32	0.34
15	Precast - Edgings flat top 50x150, bed and haunch		354	m	18.55	6,566.70
A010005082	Skilled Groundworker		0.10	hour	30.00	3.00
A010005081	Skilled Groundworks Labourer		0.10	hour	22.50	2.25
F003500050	50 x 150mm flat top pin kerb		1.05	m	4.35	4.57
F001100075	C15 IAGG Rate		0.04	m3	157.83	6.31
16	Tarmac - Roadbase under pavements, 125mm		1161	m²	99.94	116,030.34
D000200090	32mm Dense binder course		0.31	tonne	190.00	58.90
F000006076	Tarmac contractor to lay 125mm 32mm dense binder course (beneath block paving)		28.00	m2	1.00	28.00
17	Tarmac - Pavement 50/20		299	m²	69.37	20,741.63
D000200060	6mm Stone mastic asphalt SMA		0.05	tonne	210.38	10.52
D000200086	20mm Dense binder course		0.12	tonne	190.00	22.80
F000006077	Tarmac contractor to lay 50mm 20mm dense binder course (pavements)		17.00	m2	1.00	17.00
F000006090	Tarmac contractor to lay 20mm 6mm stone mastic SMA (pavements)		10.00	m2	1.00	10.00
Total for External Works						250,403.24
DRAINAGE						
Foul & Surface Water Drainage						
18	Drainage - Trench for 100/110mm pipe 500mm wide, backfill with Type 1, 1.50m deep		52	m	54.30	2,823.60
A010005089	Excavator Operator		0.20	hour	24.77	4.95
A010005081	Skilled Groundworks Labourer		0.20	hour	22.50	4.50
D000100086	Type 1 from AV Craine delivered to Douglas area by Fairgreen		1.02	tonne	23.72	24.19
G000050010	Petrol trenching foot		0.10	hour	2.19	0.22
G000010017	9 tonne excavator FOX (no fuel or operator)		0.20	hour	12.50	2.50
G000020005	9 tonne dumper FOX (without operator & fuel)		0.20	hour	7.78	1.56
G000035085	White diesel fuel		6.00	litre	1.55	9.30
Adjust above rate from 1.25 to 1.50m						
19	Drainage - Trench for 100/110mm pipe 500mm wide, backfill with Type 1, 2.00m deep		43	m	146.52	6,300.36
A010005089	Excavator Operator		0.35	hour	24.77	8.67
A010005081	Skilled Groundworks Labourer		0.35	hour	22.50	7.88
D000100086	Type 1 from AV Craine delivered to Douglas area by Fairgreen		3.29	tonne	23.72	78.04
G000050010	Petrol trenching foot		0.10	hour	2.19	0.22

Dandara - Ballasalla Phase 4 - Priced Groundwork Schedule

			Qty	Unit	Rate	R Ext £ p
G000010017	9 tonne excavator FOX (no fuel or operator)		0.35	hour	12.50	4.38
G000020005	9 tonne dumper FOX (without operator & fuel)		0.35	hour	7.78	2.72
G000035085	White diesel fuel		10.00	litre	1.55	15.50
G000070020	2400 x 900mm trench drag box		1.00	hour	10.00	10.00
	<i>Adjust above rate from 2.00 to 1.75m</i>					
20	Drainage - Trench for 150/225mm pipe 600mm wide, backfill with excavated material, 1.25m deep		82	m	30.10	2,468.20
A010005089	Excavator Operator		0.22	hour	24.77	5.45
A010005081	Skilled Groundworks Labourer		0.33	hour	22.50	7.43
G000050010	Petrol trenching foot		0.10	hour	2.19	0.22
G000010017	9 tonne excavator FOX (no fuel or operator)		0.22	hour	12.50	2.75
G000020005	9 tonne dumper FOX (without operator & fuel)		0.33	hour	7.78	2.57
G000035085	White diesel fuel		5.00	litre	1.55	7.75
	<i>Adjust above rate from 1.25 to 1.75m</i>					
21	Drainage - Trench for 150/225mm pipe 600mm wide, backfill with Type 1, 1.25m deep		44	m	68.40	3,009.60
A010005089	Excavator Operator		0.30	hour	24.77	7.43
A010005081	Skilled Groundworks Labourer		0.20	hour	22.50	4.50
D000100086	Type 1 from AV Craine delivered to Douglas area by Fairgreen		1.23	tonne	23.72	29.18
G000050010	Petrol trenching foot		0.30	hour	2.19	0.66
G000010017	9 tonne excavator FOX (no fuel or operator)		0.30	hour	12.50	3.75
G000020005	9 tonne dumper FOX (without operator & fuel)		0.20	hour	7.78	1.56
G000035085	White diesel fuel		8.00	litre	1.55	12.40
22	Drainage - Trench for 150/225mm pipe 600mm wide, backfill with Type 1, 1.50m deep		83	m	77.26	6,412.58
A010005089	Excavator Operator		0.30	hour	24.77	7.43
A010005081	Skilled Groundworks Labourer		0.20	hour	22.50	4.50
D000100086	Type 1 from AV Craine delivered to Douglas area by Fairgreen		1.55	tonne	23.72	36.77
G000050010	Petrol trenching foot		0.35	hour	2.19	0.77
G000010017	9 tonne excavator FOX (no fuel or operator)		0.30	hour	12.50	3.75
G000020005	9 tonne dumper FOX (without operator & fuel)		0.20	hour	7.78	1.56
G000035085	White diesel fuel		8.00	litre	1.55	12.40
23	Drainage - Trench for 150/225mm pipe 600mm wide, backfill with Type 1, 1.75m deep		21	m	129.93	2,728.53
A010005089	Excavator Operator		0.35	hour	24.77	8.67
A010005081	Skilled Groundworks Labourer		0.20	hour	22.50	4.50
D000100086	Type 1 from AV Craine delivered to Douglas area by Fairgreen		2.71	tonne	23.72	64.28

Dandara - Ballasalla Phase 4 - Priced Groundwork Schedule

			Qty	Unit	Rate	R Ext £ p
G000050010	Petrol trenching foot		0.45	hour	2.19	0.99
G000010017	9 tonne excavator FOX (no fuel or operator)		0.35	hour	12.50	4.38
G000020005	9 tonne dumper FOX (without operator & fuel)		0.20	hour	7.78	1.56
G000035085	White diesel fuel		12.00	litre	1.55	18.60
G000070020	2400 x 900mm trench drag box		1.00	hour	10.00	10.00
24	Drainage - Trench for 150/225mm pipe 600mm wide, backfill with Type 1, 2.00m deep		118	m	133.80	15,788.40
A010005089	Excavator Operator		0.37	hour	24.77	9.16
A010005081	Skilled Groundworks Labourer		0.22	hour	22.50	4.95
D000100086	Type 1 from AV Craine delivered to Douglas area by Fairgreen		3.29	tonne	23.72	78.04
G000050010	Petrol trenching foot		0.37	hour	2.19	0.81
G000010017	9 tonne excavator FOX (no fuel or operator)		0.37	hour	12.50	4.63
G000020005	9 tonne dumper FOX (without operator & fuel)		0.22	hour	7.78	1.71
G000035085	White diesel fuel		11.00	litre	1.55	17.05
25	Drainage - Trench for 150/225mm pipe 600mm wide, backfill with Type 1, 2.25m deep		74	m	171.70	12,705.80
A010005089	Excavator Operator		0.40	hour	24.77	9.91
A010005081	Skilled Groundworks Labourer		0.35	hour	22.50	7.88
D000100086	Type 1 from AV Craine delivered to Douglas area by Fairgreen		3.78	tonne	23.72	89.66
G000050010	Petrol trenching foot		0.40	hour	2.19	0.88
G000010017	9 tonne excavator FOX (no fuel or operator)		0.40	hour	12.50	5.00
G000020005	9 tonne dumper FOX (without operator & fuel)		0.35	hour	7.78	2.72
G000035085	White diesel fuel		15.00	litre	1.55	23.25
G000070020	2400 x 900mm trench drag box		1.00	hour	10.00	10.00
26	Drainage - 14mm granular material bed & surround 100/110mm pipe, 500x300mm		45	m	19.77	889.65
A010005089	Excavator Operator		0.05	hour	24.77	1.24
A010005081	Skilled Groundworks Labourer		0.05	hour	22.50	1.13
D000100121	10/14mm pea gravel pipe bedding aggregate delivered		0.29	tonne	43.60	12.64
G000010017	9 tonne excavator FOX (no fuel or operator)		0.05	hour	12.50	0.63
G000035085	White diesel fuel		1.00	litre	1.55	1.55
27	Drainage - 14mm granular material bed & surround 150mm pipe, 600x350mm		211	m	23.78	5,017.58
A010005089	Excavator Operator		0.05	hour	24.77	1.24
A010005081	Skilled Groundworks Labourer		0.05	hour	22.50	1.13
D000100121	10/14mm pea gravel pipe bedding aggregate delivered		0.37	tonne	43.60	16.13
G000035085	White diesel fuel		1.00	litre	1.55	1.55

Dandara - Ballasalla Phase 4 - Priced Groundwork Schedule

			Qty	Unit	Rate	R Ext £ p
G000010017	9 tonne excavator FOX (no fuel or operator)		0.05	hour	12.50	0.63
28	Drainage - 14mm granular material bed & surround 225mm pipe, 600x425mm		195	m	25.79	5,029.05
A010005089	Excavator Operator		0.05	hour	24.77	1.24
A010005081	Skilled Groundworks Labourer		0.05	hour	22.50	1.13
D000100121	10/14mm pea gravel pipe bedding aggregate delivered		0.41	tonne	43.60	17.88
G000035085	White diesel fuel		1.00	litre	1.55	1.55
G000010017	9 tonne excavator FOX (no fuel or operator)		0.05	hour	12.50	0.63
29	Drainage - C20 concrete bed & surround 100/110mm pipe, 500x300mm		45	m	37.78	1,700.10
A010005089	Excavator Operator		0.07	hour	24.77	1.73
A010005081	Skilled Groundworks Labourer		0.07	hour	22.50	1.58
F001100088	C20/25 IAGG rate		0.16	m3	165.56	26.49
G000035085	White diesel fuel		1.40	litre	1.55	2.17
G000010017	9 tonne excavator FOX (no fuel or operator)		0.07	hour	12.50	0.88
30	Drainage - C20 concrete bed & surround 150mm pipe, 600x350mm		15	m	41.58	623.70
A010005089	Excavator Operator		0.07	hour	24.77	1.73
A010005081	Skilled Groundworks Labourer		0.07	hour	22.50	1.58
F001100088	C20/25 IAGG rate		0.18	m3	165.56	29.80
G000035085	White diesel fuel		1.40	litre	1.55	2.17
G000010017	9 tonne excavator FOX (no fuel or operator)		0.07	hour	12.50	0.88
31	Drainage - C20 concrete cover slab with mesh reinforcement to 150mm pipe, 1100x150mm		29	m	53.89	1,562.81
A010005089	Excavator Operator		0.10	hour	24.77	2.48
A010005081	Skilled Groundworks Labourer		0.10	hour	22.50	2.25
F001100088	C20/25 IAGG rate		0.18	m3	165.56	29.80
F001600025	A393 6.16kg/m2 Fabric Reinforcement		1.39	m2	5.74	7.98
G000035085	White diesel fuel		2.00	litre	1.55	3.10
G000010017	9 tonne excavator FOX (no fuel or operator)		0.10	hour	12.50	1.25
32	Drainage - C20 concrete cover slab with mesh reinforcement to 225mm pipe, 1175x150mm		69	m	55.80	3,850.20
A010005089	Excavator Operator		0.10	hour	24.77	2.48
A010005081	Skilled Groundworks Labourer		0.10	hour	22.50	2.25
F001100088	C20/25 IAGG rate		0.19	m3	165.56	31.46
F001600025	A393 6.16kg/m2 Fabric Reinforcement		1.39	m2	5.74	7.98
G000035085	White diesel fuel		2.00	litre	1.55	3.10
G000010017	9 tonne excavator FOX (no fuel or operator)		0.10	hour	12.50	1.25

Dandara - Ballasalla Phase 4 - Priced Groundwork Schedule

			Qty	Unit	Rate	R Ext £ p
33	Drainage - Polypipe "Solid Wall" plastic 110mm pipe in trenches		96	m	10.07	966.72
A010005082	Skilled Groundworker		0.05	hour	30.00	1.50
W000095010	Polypipe solid wall 110mm socket spigot pipe		1.05	m	6.91	7.26
34	Drainage - Polypipe "Solid Wall" plastic 110mm pipe in trenches, bends		30	nr	11.62	348.60
A010005081	Skilled Groundworks Labourer		0.10	hour	22.50	2.25
W000095015	Polypipe solid wall 110mm double socket bends		1.00	ea	7.85	7.85
35	Drainage - Polypipe "Solid Wall" plastic 110mm pipe in trenches, rocker pipe		6	nr	18.72	112.32
A010005081	Skilled Groundworks Labourer		0.20	hour	22.50	4.50
W000095010	Polypipe solid wall 110mm socket spigot pipe		0.62	m	6.91	4.28
W000095025	Polypipe solid wall 110mm coupler		2.00	ea	3.75	7.50
36	Drainage - Polypipe "Polysewer" ribbed wall 150mm pipe in trenches		226	m	17.09	3,862.34
A010005082	Skilled Groundworker		0.07	hour	30.00	2.10
W000095030	Polypipe "Polysewer" ribbed wall 150mm socket spigot pipe		1.05	m	12.15	12.76
37	Drainage - Polypipe "Polysewer" ribbed wall 150mm pipe in trenches, bends		45	nr	46.26	2,081.70
A010005081	Skilled Groundworks Labourer		0.12	hour	22.50	2.70
W000095035	Polypipe "Polysewer" ribbed wall 150mm bends		1.00	ea	37.53	37.53
38	Drainage - Polypipe "Polysewer" ribbed wall 150mm pipe in trenches, unequal branches, 150x150x110		11	nr	72.94	802.34
A010005081	Skilled Groundworks Labourer		0.15	hour	22.50	3.38
W000095045	Polypipe "Polysewer" ribbed wall 150mm triple socket unequal branches		1.00	ea	60.05	60.05
39	Drainage - Polypipe "Polysewer" ribbed wall 150mm pipe in trenches, rocker		13	nr	58.24	757.12
A010005081	Skilled Groundworks Labourer		0.25	hour	22.50	5.63
W000095030	Polypipe "Polysewer" ribbed wall 150mm socket spigot pipe		0.63	m	12.15	7.65
W000095050	Polypipe "Polysewer" ribbed wall 150mm coupler		2.00	ea	18.68	37.36
40	Drainage - Polypipe "Polysewer" ribbed wall 225mm pipe in trenches		195	m	40.66	7,928.70
A010005082	Skilled Groundworker		0.05	hour	30.00	1.50
A010005081	Skilled Groundworks Labourer		0.05	hour	22.50	1.13

Dandara - Ballasalla Phase 4 - Priced Groundwork Schedule

			Qty	Unit	Rate	R Ext £ p
W000095055	Polypipe "Polysewer" ribbed wall 225mm socket spigot pipe		1.05	m	31.17	32.73
41	Drainage - Polypipe "Polysewer" ribbed wall 225mm pipe in trenches, bends		35	nr	197.97	6,928.95
A010005081	Skilled Groundworks Labourer		0.22	hour	22.50	4.95
W000095060	Polypipe "Polysewer" ribbed wall 225mm bends		1.00	ea	167.20	167.20
42	Drainage - Polypipe "Polysewer" ribbed wall 225mm pipe in trenches, unequal branches		10	nr	619.56	6,195.60
A010005081	Skilled Groundworks Labourer		0.30	hour	22.50	6.75
W000095065	Polypipe "Polysewer" ribbed wall 225mm triple socket unequal branches		1.00	ea	532.00	532.00
43	Drainage - Polypipe "Polysewer" ribbed wall 225mm pipe in trenches, rocker		12	nr	0.00	0.00
44	Road Gully 450x900mm with Double Triangle Ductile Iron Grating & Frame		10	nr	526.75	5,267.50
A010005082	Skilled Groundworker		4.00	hour	30.00	120.00
A010005081	Skilled Groundworks Labourer		1.00	hour	22.50	22.50
W002700005	450 x 900mm PVC-U Road Gully with 160mm outlet		1.00	nr	110.00	110.00
W002700010	580 x 465mm hinged ductile iron grate and frame		1.00	nr	120.00	120.00
F001100075	C15 IAGG Rate		0.20	m3	157.83	31.57
G000101000	Premix mortar		22.00	litre	0.32	7.04
G000200005	Class B Engineering Bricks		60.00	nr	0.65	39.00
G000020005	9 tonne dumper FOX (without operator & fuel)		0.10	hour	7.78	0.78
G000010017	9 tonne excavator FOX (no fuel or operator)		0.20	hour	12.50	2.50
G000035085	White diesel fuel		3.00	litre	1.55	4.65
45	Manhole - 1200mm dia, 1.75m depth, 150mm		2	nr	3832.34	7,664.68
A010005082	Skilled Groundworker		16.00	hour	30.00	480.00
A010005081	Skilled Groundworks Labourer		16.00	hour	22.50	360.00
W002200035	Step Irons in PCC MH Units		6.00	nr	25.00	150.00
G000200005	Class B Engineering Bricks		80.00	nr	0.65	52.00
G000101000	Premix mortar		40.00	litre	0.32	12.80
W002200180	1200mm diameter PCC MH wide wall 500mm ring		1.00	nr	284.94	284.94
W002200190	1200mm diameter PCC MH wide wall 1000mm ring		1.00	nr	424.76	424.76
W002200195	Tokstrip 80 x 12 x 8000mm		12.00	m	10.00	120.00
W002200115	1200mm diameter PCC MH Cover Slab		1.00	nr	205.25	205.25
F001100075	C15 IAGG Rate		1.20	m3	157.83	189.40

Dandara - Ballasalla Phase 4 - Priced Groundwork Schedule

			Qty	Unit	Rate	R Ext £ p
W002900062	Ductile iron 600 x 600x 10mm double tri manhole cover D400 grade		1.00	nr	300.00	300.00
N004900095	18mm CDX plywood		2.00	m2	6.94	13.88
N001500205	50 X 100mm Sawn SW G S Grade		20.00	m	1.78	35.60
N015404000	Sundry fixings		10.00	£	1.00	10.00
D000100088	Type 1 from AV Craine delivered to Peel area by Fairgreen		1.20	tonne	23.72	28.46
D000100124	Grano dust		0.25	tonne	85.00	21.25
D000100106	Building Sand to Peel area by Fairgreen		0.50	tonne	31.33	15.67
W002300035	Sundry clay channels		250.00	£	1.00	250.00
W002300040	Sundry rigid board insulation for formwork to channels		25.00	£	1.00	25.00
F000200026	25Kg OPC		4.00	bag	5.50	22.00
G000020005	9 tonne dumper FOX (without operator & fuel)		1.00	hour	7.78	7.78
G000035085	White diesel fuel		140.00	litre	1.55	217.00
G000010003	21 tonne excavator FOX (no fuel)		6.00	hour	17.78	106.68
46	2.00m depth, 150mm		2	nr	4101.92	8,203.84
A010005082	Skilled Groundworker		20.00	hour	30.00	600.00
A010005081	Skilled Groundworks Labourer		16.00	hour	22.50	360.00
W002200035	Step Irons in PCC MH Units		8.00	nr	25.00	200.00
G000200005	Class B Engineering Bricks		80.00	nr	0.65	52.00
G000101000	Premix mortar		40.00	litre	0.32	12.80
W002200185	1200mm diameter PCC MH wide wall 750mm ring		1.00	nr	349.36	349.36
W002200190	1200mm diameter PCC MH wide wall 1000mm ring		1.00	nr	424.76	424.76
W002200195	Tokstrip 80 x 12 x 8000mm		12.00	m	10.00	120.00
W002200115	1200mm diameter PCC MH Cover Slab		1.00	nr	205.25	205.25
F001100075	C15 IAGG Rate		1.20	m3	157.83	189.40
W002900062	Ductile iron 600 x 600x 10mm double tri manhole cover D400 grade		1.00	nr	300.00	300.00
N004900095	18mm CDX plywood		2.00	m2	6.94	13.88
N001500205	50 X 100mm Sawn SW G S Grade		20.00	m	1.78	35.60
N015404000	Sundry fixings		10.00	£	1.00	10.00
D000100088	Type 1 from AV Craine delivered to Peel area by Fairgreen		1.20	tonne	23.72	28.46
D000100124	Grano dust		0.25	tonne	85.00	21.25
D000100106	Building Sand to Peel area by Fairgreen		0.50	tonne	31.33	15.67
W002300035	Sundry clay channels		250.00	£	1.00	250.00
W002300040	Sundry rigid board insulation for formwork to channels		25.00	£	1.00	25.00
F000200026	25Kg OPC		4.00	bag	5.50	22.00
G000020005	9 tonne dumper FOX (without operator & fuel)		1.00	hour	7.78	7.78

Dandara - Ballasalla Phase 4 - Priced Groundwork Schedule

			Qty	Unit	Rate	R Ext £ p
G000035085	White diesel fuel		140.00	litre	1.55	217.00
G000010003	21 tonne excavator FOX (no fuel)		6.00	hour	17.78	106.68
47	2.25m depth, 150mm		10	nr	4376.98	43,769.80
A010005082	Skilled Groundworker		20.00	hour	30.00	600.00
A010005081	Skilled Groundworks Labourer		20.00	hour	22.50	450.00
W002200035	Step Irons in PCC MH Units		9.00	nr	25.00	225.00
G000200005	Class B Engineering Bricks		80.00	nr	0.65	52.00
G000101000	Premix mortar		40.00	litre	0.32	12.80
W002200190	1200mm diameter PCC MH wide wall 1000mm ring		2.00	nr	424.76	849.52
W002200195	Tokstrip 80 x 12 x 8000mm		12.00	m	10.00	120.00
W002200115	1200mm diameter PCC MH Cover Slab		1.00	nr	205.25	205.25
F001100075	C15 IAGG Rate		1.20	m3	157.83	189.40
W002900062	Ductile iron 600 x 600x 10mm double tri manhole cover D400 grade		1.00	nr	300.00	300.00
N004900095	18mm CDX plywood		2.00	m2	6.94	13.88
N001500205	50 X 100mm Sawn SW G S Grade		20.00	m	1.78	35.60
N015404000	Sundry fixings		10.00	£	1.00	10.00
D000100088	Type 1 from AV Craine delivered to Peel area by Fairgreen		1.20	tonne	23.72	28.46
D000100124	Grano dust		0.25	tonne	85.00	21.25
D000100106	Building Sand to Peel area by Fairgreen		0.50	tonne	31.33	15.67
W002300035	Sundry clay channels		250.00	£	1.00	250.00
W002300040	Sundry rigid board insulation for formwork to channels		25.00	£	1.00	25.00
F000200026	25Kg OPC		4.00	bag	5.50	22.00
G000020005	9 tonne dumper FOX (without operator & fuel)		1.00	hour	7.78	7.78
G000035085	White diesel fuel		160.00	litre	1.55	248.00
G000010003	21 tonne excavator FOX (no fuel)		7.00	hour	17.78	124.46
48	Extra over for recesss manhole covers		10	nr	0.00	0.00
49	Manhole - 1350mm dia, 1.25m depth, 225mm		2	nr	4466.49	8,932.98
A010005082	Skilled Groundworker		20.00	hour	30.00	600.00
A010005081	Skilled Groundworks Labourer		20.00	hour	22.50	450.00
W002200035	Step Irons in PCC MH Units		4.00	nr	25.00	100.00
G000200005	Class B Engineering Bricks		80.00	nr	0.65	52.00
G000101000	Premix mortar		40.00	litre	0.32	12.80
W002200195	Tokstrip 80 x 12 x 8000mm		12.00	m	10.00	120.00
F001100075	C15 IAGG Rate		1.20	m3	157.83	189.40

Dandara - Ballasalla Phase 4 - Priced Groundwork Schedule

			Qty	Unit	Rate	R Ext £ p
W002900062	Ductile iron 600 x 600x 10mm double tri manhole cover D400 grade		1.00	nr	300.00	300.00
N004900095	18mm CDX plywood		2.00	m2	6.94	13.88
N001500205	50 X 100mm Sawn SW G S Grade		20.00	m	1.78	35.60
N015404000	Sundry fixings		10.00	£	1.00	10.00
D000100088	Type 1 from AV Craine delivered to Peel area by Fairgreen		1.20	tonne	23.72	28.46
D000100124	Grano dust		1.00	tonne	85.00	85.00
D000100106	Building Sand to Peel area by Fairgreen		3.00	tonne	31.33	93.99
W002300035	Sundry clay channels		500.00	£	1.00	500.00
W002300040	Sundry rigid board insulation for formwork to channels		25.00	£	1.00	25.00
F000200026	25Kg OPC		16.00	bag	5.50	88.00
W002200200	1350mm diameter PCC MH wide wall 250mm ring		1.00	nr	170.25	170.25
W002200215	1350mm diameter PCC MH wide wall 1000mm ring		1.00	nr	325.25	325.25
W002200216	1350mm diameter PCC MH Cover Slab		1.00	nr	255.25	255.25
G000020005	9 tonne dumper FOX (without operator & fuel)		1.00	hour	7.78	7.78
G000035085	White diesel fuel		180.00	litre	1.55	279.00
G000010003	21 tonne excavator FOX (no fuel)		8.00	hour	17.78	142.24
<i>Change from 1.50m to 1.25m and pipe size to 225mm</i>						
50	1.50m depth, 225mm		2	nr	4800.63	9,601.26
A010005082	Skilled Groundworker		22.00	hour	30.00	660.00
A010005081	Skilled Groundworks Labourer		22.00	hour	22.50	495.00
W002200035	Step Irons in PCC MH Units		6.00	nr	25.00	150.00
G000200005	Class B Engineering Bricks		80.00	nr	0.65	52.00
G000101000	Premix mortar		40.00	litre	0.32	12.80
W002200195	Tokstrip 80 x 12 x 8000mm		12.00	m	10.00	120.00
F001100075	C15 IAGG Rate		1.20	m3	157.83	189.40
W002900062	Ductile iron 600 x 600x 10mm double tri manhole cover D400 grade		1.00	nr	300.00	300.00
N004900095	18mm CDX plywood		2.00	m2	6.94	13.88
N001500205	50 X 100mm Sawn SW G S Grade		20.00	m	1.78	35.60
N015404000	Sundry fixings		10.00	£	1.00	10.00
D000100088	Type 1 from AV Craine delivered to Peel area by Fairgreen		1.20	tonne	23.72	28.46
D000100124	Grano dust		1.00	tonne	85.00	85.00
D000100106	Building Sand to Peel area by Fairgreen		3.00	tonne	31.33	93.99
W002300035	Sundry clay channels		500.00	£	1.00	500.00
W002300040	Sundry rigid board insulation for formwork to channels		25.00	£	1.00	25.00
F000200026	25Kg OPC		16.00	bag	5.50	88.00

Dandara - Ballasalla Phase 4 - Priced Groundwork Schedule

			Qty	Unit	Rate	R Ext £ p
W002200205	1350mm diameter PCC MH wide wall 500mm ring		1.00	nr	218.25	218.25
W002200215	1350mm diameter PCC MH wide wall 1000mm ring		1.00	nr	325.25	325.25
W002200216	1350mm diameter PCC MH Cover Slab		1.00	nr	255.25	255.25
G000020005	9 tonne dumper FOX (without operator & fuel)		2.00	hour	7.78	15.56
G000035085	White diesel fuel		220.00	litre	1.55	341.00
G000010003	21 tonne excavator FOX (no fuel)		9.00	hour	17.78	160.02
<i>Change from 1.75m to 1.50m and pipe size to 225mm</i>						
51	2.00m depth, 225mm		2	nr	5189.58	10,379.16
A010005082	Skilled Groundworker		24.00	hour	30.00	720.00
A010005081	Skilled Groundworks Labourer		24.00	hour	22.50	540.00
W002200035	Step Irons in PCC MH Units		8.00	nr	25.00	200.00
G000200005	Class B Engineering Bricks		80.00	nr	0.65	52.00
G000101000	Premix mortar		40.00	litre	0.32	12.80
W002200195	Tokstrip 80 x 12 x 8000mm		12.00	m	10.00	120.00
F001100075	C15 IAGG Rate		1.20	m3	157.83	189.40
W002900062	Ductile iron 600 x 600x 10mm double tri manhole cover D400 grade		1.00	nr	300.00	300.00
N004900095	18mm CDX plywood		2.00	m2	6.94	13.88
N001500205	50 X 100mm Sawn SW G S Grade		20.00	m	1.78	35.60
N015404000	Sundry fixings		10.00	£	1.00	10.00
D000100088	Type 1 from AV Craine delivered to Peel area by Fairgreen		1.20	tonne	23.72	28.46
D000100124	Grano dust		3.00	tonne	85.00	255.00
D000100106	Building Sand to Peel area by Fairgreen		3.00	tonne	31.33	93.99
W002300035	Sundry clay channels		500.00	£	1.00	500.00
W002300040	Sundry rigid board insulation for formwork to channels		25.00	£	1.00	25.00
F000200026	25Kg OPC		16.00	bag	5.50	88.00
W002200210	1350mm diameter PCC MH wide wall 750mm ring		1.00	nr	270.25	270.25
W002200215	1350mm diameter PCC MH wide wall 1000mm ring		1.00	nr	325.25	325.25
W002200216	1350mm diameter PCC MH Cover Slab		1.00	nr	255.25	255.25
G000020005	9 tonne dumper FOX (without operator & fuel)		1.00	hour	7.78	7.78
G000035085	White diesel fuel		200.00	litre	1.55	310.00
G000010003	21 tonne excavator FOX (no fuel)		9.00	hour	17.78	160.02
<i>Change from 2.00m to 1.75m and pipe size to 225mm</i>						
52	E.O. backdrop to existing manhole		1	nr	0.00	0.00
53	Break into existing foul main sewer		2	nr	713.29	1,426.58
A010005082	Skilled Groundworker		8.50	hour	30.00	255.00
A010005081	Skilled Groundworks Labourer		8.50	hour	22.50	191.25

Dandara - Ballasalla Phase 4 - Priced Groundwork Schedule

			Qty	Unit	Rate	R Ext £ p
G000035085	White diesel fuel		80.00	litre	1.55	124.00
G000010017	9 tonne excavator FOX (no fuel or operator)		4.00	hour	12.50	50.00
54	Disposal of surface water		1	nr	0.00	0.00
55	CCTV survey & record DVDs		517	m	5.75	2,972.75
56	Jetting drains prior to adoption (regardless of size)		517	m	2.30	1,189.10
Total for Drainage						200,302.20
SERVICES						
Electric						
57	Service trenches - for cable/duct, 500mm wide,1 Nr red duct, tape, 750mm deep		10	m	42.65	426.50
A010005089	Excavator Operator		0.10	hour	24.77	2.48
A010005081	Skilled Groundworks Labourer		0.20	hour	22.50	4.50
W003300050	Warning tape		1.10	m	0.11	0.12
W003300051	Blue polythene draw rope		1.10	m	0.07	0.08
W003300020	125mm red electrical rigiduct S/S		1.05	m	12.22	12.83
D000100106	Building Sand to Peel area by Fairgreen		0.30	tonne	31.33	9.40
G000050010	Petrol trenching foot		0.10	hour	2.19	0.22
G000010017	9 tonne excavator FOX (no fuel or operator)		0.10	hour	12.50	1.25
G000020005	9 tonne dumper FOX (without operator & fuel)		0.20	hour	7.78	1.56
G000035085	White diesel fuel		3.00	litre	1.55	4.65
58	Service trenches - for cable/duct, 500mm wide,2 Nr red duct, tape, 750mm deep		8	nr	0.00	0.00
59	Service trenches - for cable/duct, 500mm wide,2 Nr red duct, tape, 750mm deep		3	nr	0.00	0.00
60	Service trenches - for cable/duct, 500mm wide, red duct, tape, 1500mm deep, road crossings		12	m	94.43	1,133.16
A010005089	Excavator Operator		0.20	hour	24.77	4.95
A010005081	Skilled Groundworks Labourer		0.40	hour	22.50	9.00
D000100086	Type 1 from AV Craine delivered to Douglas area by Fairgreen		1.29	tonne	23.72	30.60
W003300050	Warning tape		1.10	m	0.11	0.12
W003300051	Blue polythene draw rope		1.10	m	0.07	0.08
W003300020	125mm red electrical rigiduct S/S		1.05	m	12.22	12.83
D000100106	Building Sand to Peel area by Fairgreen		0.30	tonne	31.33	9.40
G000050010	Petrol trenching foot		0.10	hour	2.19	0.22
G000010017	9 tonne excavator FOX (no fuel or operator)		0.20	hour	12.50	2.50
G000020005	9 tonne dumper FOX (without operator & fuel)		0.40	hour	7.78	3.11
G000035085	White diesel fuel		6.00	litre	1.55	9.30

Dandara - Ballasalla Phase 4 - Priced Groundwork Schedule

			Qty	Unit	Rate	R Ext £ p
61	Mains Water Service trenches - for cable/duct, 500mm wide, blue duct/pipe, tape, 1500mm deep, road crossings		17	m	86.81	1,475.77
A010005089	Excavator Operator		0.20	hour	24.77	4.95
A010005081	Skilled Groundworks Labourer		0.40	hour	22.50	9.00
D000100086	Type 1 from AV Craine delivered to Douglas area by Fairgreen		1.26	tonne	23.72	29.89
W003300050	Warning tape		1.10	m	0.11	0.12
W003300051	Blue polythene draw rope		1.10	m	0.07	0.08
D000100106	Building Sand to Peel area by Fairgreen		0.30	tonne	31.33	9.40
G000050010	Petrol trenching foot		0.10	hour	2.19	0.22
G000010017	9 tonne excavator FOX (no fuel or operator)		1.00	hour	12.50	12.50
G000020005	9 tonne dumper FOX (without operator & fuel)		1.00	hour	7.78	7.78
G000035085	White diesel fuel		1.00	litre	1.55	1.55
62	Service trenches - for cable/duct, 500mm wide, blue duct/pipe, tape, 750mm deep		21	m	27.90	585.90
A010005089	Excavator Operator		0.10	hour	24.77	2.48
A010005081	Skilled Groundworks Labourer		0.20	hour	22.50	4.50
W003300050	Warning tape		1.10	m	0.11	0.12
W003300051	Blue polythene draw rope		1.10	m	0.07	0.08
D000100106	Building Sand to Peel area by Fairgreen		0.30	tonne	31.33	9.40
G000050010	Petrol trenching foot		0.10	hour	2.19	0.22
G000010017	9 tonne excavator FOX (no fuel or operator)		0.10	hour	12.50	1.25
G000020005	9 tonne dumper FOX (without operator & fuel)		0.20	hour	7.78	1.56
G000035085	White diesel fuel		3.00	litre	1.55	4.65
63	Telecom Service trenches - for cable/duct, 500mm wide, orange duct/pipe, tape, 750mm deep		0	m	27.90	0.00
A010005089	Excavator Operator		0.10	hour	24.77	2.48
A010005081	Skilled Groundworks Labourer		0.20	hour	22.50	4.50
W003300050	Warning tape		1.10	m	0.11	0.12
W003300051	Blue polythene draw rope		1.10	m	0.07	0.08
D000100106	Building Sand to Peel area by Fairgreen		0.30	tonne	31.33	9.40
G000050010	Petrol trenching foot		0.10	hour	2.19	0.22
G000010017	9 tonne excavator FOX (no fuel or operator)		0.10	hour	12.50	1.25
G000020005	9 tonne dumper FOX (without operator & fuel)		0.20	hour	7.78	1.56
G000035085	White diesel fuel		3.00	litre	1.55	4.65

Dandara - Ballasalla Phase 4 - Priced Groundwork Schedule

			Qty	Unit	Rate	R Ext £ p
64	Assumes 1 Nr 54mm MT duct supplied free issue, only bedded and surrounded in sand, draw cord and warning tape; backfilled with as dug material, excess material carted to onsite spoil heaps max 250m from excavation Service trenches - for cable/duct, 500mm wide, yellow duct, tape, 1500mm deep, road crossings		0	m	86.81	0.00
A010005089	Excavator Operator		0.20	hour	24.77	4.95
A010005081	Skilled Groundworks Labourer		0.40	hour	22.50	9.00
D000100086	Type 1 from AV Craine delivered to Douglas area by Fairgreen		1.26	tonne	23.72	29.89
W003300050	Warning tape		1.10	m	0.11	0.12
W003300051	Blue polythene draw rope		1.10	m	0.07	0.08
D000100106	Building Sand to Peel area by Fairgreen		0.30	tonne	31.33	9.40
G000050010	Petrol trenching foot		0.10	hour	2.19	0.22
G000010017	9 tonne excavator FOX (no fuel or operator)		1.00	hour	12.50	12.50
G000020005	9 tonne dumper FOX (without operator & fuel)		1.00	hour	7.78	7.78
G000035085	White diesel fuel		1.00	litre	1.55	1.55
65	Assumes 1 Nr 54mm MT duct supplied free issue, only bedded and surrounded in sand, draw cord and warning tape; backfilled with Type 1 material, excess material carted to onsite spoil heaps max 250m from excavation Service Trench - telecom chamber		0	nr	683.58	0.00
A010005082	Skilled Groundworker		2.00	hour	30.00	60.00
A010005081	Skilled Groundworks Labourer		1.00	hour	22.50	22.50
F001100096	C28/35 KCL 2025 rate		0.50	m3	176.79	88.40
W003300330	450 x 450 NAL STAKKAbox 1 Riser Section x 155mm		3.00	nr	37.06	111.18
W003300335	450 x 450 NAL STAKKAbox 1 Access Section x 155mm		1.00	nr	65.00	65.00
W003300340	450 x 450 x 85mm C250 Hi-Top Composite Cover and frame		1.00	nr	225.00	225.00
G000010022	3 tonne excavator FOX (no feul or operator)		1.00	hour	8.33	8.33
G000035085	White diesel fuel		2.00	litre	1.55	3.10
Y000010010	Cart and tip inert excavated material from Douglas area at Fairgreen Tip (loading wagons by Main Contractor machine)		0.70	tonne	15.58	10.91
	Nal box 750mm deep with cover					
	Total for Services					3,621.33
66	STREET LIGHTING Service trenches - for cable/duct, 500mm wide, orange/purple duct, tape, 750mm deep		116	m	0.00	0.00

Dandara - Ballasalla Phase 4 - Priced Groundwork Schedule

			Qty	Unit	Rate	R Ext £ p
67	Service trenches - for cable/duct (2nr), 500mm wide, orange/purple duct, tape, 750mm deep		18	m	0.00	0.00
68	Service trenches - for cable/duct, 500mm wide, orange/purple duct, tape, 1500mm deep, road crossings		96	m	0.00	0.00
69	Service trenches - for cable/duct, 500mm wide, orange/purple duct (2nr), tape, 1500mm deep, road crossings		9	m	0.00	0.00
Total for Street Lighting						0.00
Total for Bill						454,326.77