

↳ dandara

↳ dandara

**Scope of Works –
Groundworks
BA4 Parkfield**

1. GENERAL

The Sub-Contractor shall provide all labour, plant, materials, supervision and temporary works necessary to carry out and complete the groundworks package in accordance with the contract documents.

2. SITE PREPARATION & EARTHWORKS

- Reduced level excavation
- Disposal of material (on-site)
- Formation preparation and compaction
- Supply and placement of Type 1 and 6F2
- Geotextile installation

3. DRAINAGE WORKS

- Trench excavation (100mm–225mm pipes)
- Pipe installation (110mm, 150mm, 225mm)
- Bedding, surround and concrete protection
- Manholes (1200mm & 1350mm)
- Gullies and connections
- Break-ins to existing sewers
- CCTV, jetting and air testing each run and providing evidence of the results
- Lateral drains to plot boundaries brought beyond the back line of the footpath into plot boundaries and capped off, with marker pegs to denote location

4. EXTERNAL WORKS

- Sub-base and capping layers as determined by CBR testing
- Kerbs and edgings (all types)
- Road construction including asphalt to form block paving sub-base
- Footpaths formed to tarmac asphalt level

5. SERVICE TRENCHES

- Excavation for electric, water, telecoms, stock pile arisings
- Installation of ducts, sand surround, tapes. All service ducts to be roped, sanded and marker tape laid
- Joint pits and chambers
- Combined service trenches

6. STREET LIGHTING

- Duct installation and trenching. All ducts to be roped, sanded and marker tape laid

7. PRELIMINARIES

- Site management and supervision
- Setting out
- Plant, temporary works, H&S
- Dust suppression and site maintenance

8. TESTING & ADOPTION

- CBR testing
- Drainage testing and CCTV
- Compliance with adoptable roads specification

9. EXCLUSIONS

- Statutory connection fees
- Final utility connections
- Abnormal ground conditions
- Dewatering unless stated

10. CLARIFICATIONS

- Scope based on drawings, BoQ and specification
- Minor discrepancies deemed included